

HAMPTON VA

Resolution in Support of the
Virginia Department of
Transportation (VDOT)
Preferred Design Alternative 2
(Bridge West with the
Causeway Remaining) for the
Route 172 Wythe Creek Road
Widening Project

October 11, 2017



- Project is administered by VDOT
- Geographically located in the cities of Hampton and Poquoson
- Improves congestion around NASA/Langley



Project History

- City Council requested VDOT to add the project to the Six-Year Improvement Plan on July 15, 2010
- Staff endorsed the design by letter on March 3, 2015
- City Council endorsed the present design on December 14, 2016

Current Project Status

- Project Under ROW Acquisition
- Anticipated Completion:

Hampton - June 2018

Poquoson - December 2019

Remaining Project Schedule

Utility Relocations

Hampton - July 2018 to October 2019

Poquoson – January 2020 to January 2021

Construction

Advertise Project September 2019



Remaining Key Design Steps

Environmental Permitting
Final Design of New Bridge Structure
Final Design of Public Utility Relocations

Environmental Permitting

Individual Permit Required (DEQ); as well as Permit from USACE and VMRC

Anticipate Initial Permit Submission to Agencies Q4 2017 w/Permitting Completion in Q4 2018/Q1 2019

Primary Environmental Impacts Associated with New Bridge Crossing Compensatory Mitigation Required

Anticipated Agency Focus on Future of Existing Causeway



Wetland/Waters Impacts

Permanent Tidal Wetland Impacts

Fill (Bridge Piers/Road Widening Cary's Chapel): 0.17 ac.

Shading Impacts (DEQ): 1.12 ac.

Permanent Forested Wetland Impacts: 0.02 ac.

Permanent Emergent Wetland Impacts (non-roadside ditch): 0.01 ac.

Tidal Waters Impacts: 0.01 ac.

Minor Temporary Impacts: 0.14-ac

Environmental Permitting

Individual Permit from DEQ; NWP from USACE; VGP from VMRC Compensatory Mitigation: Payment to VA Aquatic Resources Trust Fund

Alternative Alignments (east/west) Have Same Degree of Impacts

No Threatened/Endangered Species Impacts

Causeway Crossing Alternatives Studied:

Alternative 1 - Bridge West/Causeway Removal

Alternative 2 - Bridge West/Causeway Remains

Alternative 3 - Bridge East/Causeway Removal

Alternative 4 - Bridge East/Causeway Remains

Alternative 5 - Earthen Causeway

Alternative 6 - No-Build

Alternative 7 - Temp. Traffic Bridge/New Bridge over

Existing Causeway

Alternative 2 is Preferred Alternative as it is:

- a) Least costly option
- b) Shortest construction duration
- Does not require relocation of businesses in Poquoson/Additional impacts to NASA property



Impacts Related to Alternatives that Include Removal of Causeway:

- Cost Impact: \$12 million cost increase
- Pedestrians and bicyclists would be located on the bridge, next to traffic (no separation)
- Utilities Currently Located in/along Causeway Require Relocation – HRSD Force Main, Verizon Duct Bank, Gas Main
- Wider Bridge Required
- Loss of community amenity
- Redesign

Impacts Related to Alternatives that Bridge to East:

- Business Displacements in Poquoson
- Additional Property Impacts to NASA
- Additional Project Cost




Eastern Alignment Alternatives Require Displacements in Poquoson







Alternative 2 Layout





Alternative 2 Section View







Current Project Estimate & Funding VDOT SYIP (FY 18-23)

Hampton (UPC 97715)

| | Estimate | Funding |
|------------------------------|-----------------|---------|
| Preliminary Engineering (PE) | \$3.1m | \$3.1m |
| Right-of-Way (RW) | \$3.9m | \$3.9m |
| Construction (CN) | \$22.7m | \$22.7m |
| Total | \$29.8m | \$29.8m |

Poquoson (UPC 13427)

| | Estimate | <u>Funding</u> |
|------------------------------|-----------------|-----------------|
| Preliminary Engineering (PE) | \$1.9m | \$1.9m |
| Right-of-Way (RW) | \$5.4m | \$5.4m |
| Construction (CN) | \$12.5m | \$12.5m |
| Total | \$19.8m | \$19.8 <u>m</u> |



In Conclusion

We request that City Council approve the resolution of support for the current project design / Preferred Alternative 2 (Bridge West with the Causeway Remaining).

Questions?